

NuMI Profile Monitors

Gianni Tassotto/Robert Webber

Charge to Committee

- **assess whether the technical, resource and schedule aspects of instrumentation is sufficiently developed** to commission the NuMI beamline in January 2005.
- **Are specifications defined** and founded on a good technical basis?
- Do all sub-systems have a **clearly defined project manager and resource loaded schedule?** Are there **clearly defined milestones** for key tasks?
- **Are BD Instrumentation Dept resources sufficient** to complete NUMI instrumentation and have it completely checked out and operational on schedule for commissioning **while meeting other program instrumentation needs?**
- **Is a parallel design path for the beam profile monitor advisable?** Is there sufficient technical and resource **confidence** in 1) the "thin multi-wire" design or the "thin foil" design and 2) the "rotary insertion" design or the "bayonet insertion" design to **warrant an immediate decision?**


Outline of this Presentation

- Requirements reference
 - Geography
 - Device itemization and provider
 - Multi-wires for baseline plan
 - Plan B presentation
 - Technical considerations
 - Cost and Schedule
 - Concerns and Conclusions
-
- Note: Plan B presentation represents the technical understanding and estimates of Fermilab BD Instrumentation. It does not address impacts the plan change might have on UT costs, schedules or deliverables.

Requirements References

- NUMI Technical Design Handbook – section 4.1.3, revision date 12/05/02
- Childress memo to email distribution received 10/2/03 describing “Proposed Plan”

Profile Monitor Layout



12 devices over 1200 ft. beamline

Baseline Plan

Name in Enclosure	Baseline Plan	Distance from Q608 in Feet
PM101	UT 1 mm SEM	65.0
PM105	UT 1 mm SEM	192.4
PM107	UT 1 mm SEM	305.5
PM108	UT 1 mm SEM	362.1
PM111	FNAL 1 mm x 3 mil MW	529.9
PM112	UT 1 mm SEM	559.9
PM114	UT 1 mm SEM	810.1
PM115	UT 1 mm SEM	859.0
PM117	UT 1 mm SEM	968.3
PM118	FNAL 1 mm x 3 mil MW	1,003.8
PM121	UT 0.5 mm SEM	1,143.9
PMTGT	UT 0.5 mm SEM	1,184.8

Baseline Plan

- Fermilab provides:
 - 2 standard multiwires with 0.003” wires at 1mm pitch
 - Standard SWIC scanner readout electronics for both Fermilab and UT devices
 - Motion control electronics for both Fermilab and UT devices
 - Cabling, installation, and utilities support
 - Some support for UT devices
 - Survey/alignment fiducialization?
 - Vacuum testing?
 - ??

“Standard” Profile Monitor

- Round vacuum can with 6” top flange.
- 4 or 6” beam tube vacuum quick disconnect flanges
- NOR-CAL 4 1/2” CF flange on bottom of can for ion pump
- Varian rotary feedthrough.
- 50 pin CeramTec electrical feedthrough for wire plane signals.
- HV feedthrough for bias foils.
- **Vacuum performance:** The chamber is tested for installation at 10^{-8} Torr using a 30 l/sec ion pump before installation in beamline.



“Standard” Wire Plane Assembly


- Material: Ceramic frame.
- X, Y wire planes made using 0.003” wire soldered to printed pads on either side of ceramic frame.
- Wire: AuW 2% Re wire made by California Fine Wire.
- Wire pitch: choice of 0.5, 1 and 2 mm.
- Wire tension 80 g at winding.
- Kapton ribbon cables carry signals from wire planes to feedthroughs.
- No bias foils
 - KTeV tests show no effect on signal
 - CERN has evidence of better signal stability at high beam intensities with bias foils





Standard Readout

- FNAL made 96 channel integrator.
- Integration time from 5 μ sec - 6.5 sec.
- Dynamic range: $\cong E^{10}$ to $>10^{13}$ ppp
- 16 bit ADC.
- Noise $\cong 0.2\%$ of full scale.
- Calibration feature.

Controls



Integrate Cycle



Baseline Plan Fermilab Status

- Fermilab provided equipment:
 - Fermilab Multiwires (BD Instrumentation)
 - All parts on hand or in procurement
 - Readout Electronics (BD Controls)
 - 8/12 fabricated, 6/12 installed, 4/12 currently in fabrication
 - Motion Control for Fermilab Multiwires (BD Instrumentation)
 - Everything is on Gianni's shelf in wait
 - Motion Control for UT SEM Profile Monitors (BD Instrumentation)
 - Awaiting information
 - M&S expenses for 2 multiwires are already nearly 100% costed
- Fermilab provided support for UT SEMs
 - Preparing to install SEM in MiniBooNE beamline this shutdown
 - Anything else from Sacha's talk

Fermilab Fermilab Effort Remaining (Baseline)

- Gianni Tassotto, project manager
 - BD Instrumentation (management, assembly, install, UT device support) :
 - Gianni Tassotto - 40% through Sept '04
 - Engineering Dan Schoo - 25% through Sept '04
 - Technician Rick Pierce - 25% through Sept '04.
 - PPD or BD Vacuum Support (vacuum certification of beamline devices)
 - 1+ day per device
 - Alignment Group Measurement and Fiducialization
 - Ed Dijak? – 1-2 days per device after assembly and $\frac{1}{4}$ day per device after installation in beamline
 - BD Mechanical Department
 - 2 technicians - 1 week during installation in summer '04
 - BD Controls (signal readout and motion control)
 - Al Franck/ Joe Gomilar – 1 month readout fabrication/installation
 - Al Legan – 1 month motion control electronics procure/assemble/install

Plan B

Name in Enclosure	Baseline Plan	Proposed Plan B	Distance from Q608 in Feet
PM101	UT 1mm SEM	modified FNAL 1mm x 1 mil MW	65.0
PM105	UT 1mm SEM	modified FNAL 1mm x 1 mil MW	192.4
PM107	UT 1mm SEM	modified FNAL 1mm x 1 mil MW	305.5
PM108	UT 1mm SEM	modified FNAL 1mm x 1 mil MW	362.1
PM111	FNAL 1mm x 3 mil MW	UT linear drive foil assembly	529.9
PM112	UT 1mm SEM	modified FNAL 1mm x 1 mil MW	559.9
PM114	UT 1mm SEM	UT 1mm SEMw/FNAL can & motor	810.1
PM115	UT 1mm SEM	UT 1mm SEMw/FNAL can & motor	859.0
PM117	UT 1mm SEM	UT 1mm SEMw/FNAL can & motor	968.3
PM118	FNAL 1mm x 3 mil MW	UT linear drive foil assembly	1,003.8
PM121	UT 0.5mm SEM	UT 0.5mm SEMw/FNAL can & motor	1,143.9
PMTGT	UT 0.5mm SEM	UT 0.5mm SEMw/FNAL can & motor	1,184.8

NuMI Multiwire Specifications

- Allowable fractional beam loss $< 10^{-5}$ per detector (2 planes).
- Insertable/Removable without exceeding allowable beam loss.
- Position & Stability : 50 μm .
- Vacuum: 10^{-8} Torr using a 30 l/sec ion pump.
- Standard Fermilab readout.
- Wire pitch: 1 mm x, y planes except 0.5 mm for two multiwires immediately upstream of target.
- Capability for bias foils.


To Support the Plan

- Reduce wire diameter from 0.003” to 0.001” to reduce beam loss
- Design open-sided wire frame to permit “live” insertion/retraction
- Add 5um thick bias foils with beam clearance hole
- Design stand to accommodate 45⁰ mounting required by open-sided frame with H/V wires
- Verify 50 um positioning repeatability
- Provide estimate of cost and manpower for modified plan

Ceramic Wire Frame Modifications

- The drawing shows the open frame design to satisfy the NuMI insertion requirement.
- Plan to pre-stress frame before wires are attached.
- Open edge is at 45° to wires
- Frame is mounted square (normal) in vacuum can, can is mounted at 45° to present horizontal/vertical wires to beam.



- **Ceramic frame with pads at 45° .**



Fermilab Wire Tension Test for Open Frame Assembly

- Wire tension before and after cutting side of existing ceramic board with wires already attached.

- Applied 14 lbs to one edge. Dial indicator showed no change at sensitivity better than 0.001"



Thermal Analysis

- Nikolai Mokhov, using MARS, has calculated peak instantaneous temperature rise for 0.003" Gold-Tungsten and Carbon wires for multiwires in the NuMI beamlines. Results here are for a 120 GeV beam at 3×10^{13} ppp.
- Maximum Delta_T (degrees C) in central (wire-1) and next three (wire-2, wire-3, wire-4) wires are presented below.

Beam	Material	Beam Sigma (mm)	wire-1	wire-2	wire-3	wire-4
NuMI	W	1	779.0	468.1	110.4	11.0
	W	2	211.7	181.8	26.5	67.1
	C	1	223.4	135.2	34.7	2.8
	C	2	72.1	57.8	40.4	21.7

- These calculations will be repeated for a 0.001" AuW wire. We have no experience using carbon wires in multiwires.
- For W, allowable temperature for 50 grams tension = 1000^0 C. (maintain 15 Kpsi yield strength).

Insertion Repeatability

- The alignment group made several measurements of the IN position of all the MiniBooNE multiwires.
- The measurements were performed at the alignment building using a ceramic frame to support the wire plane assembly. The wire plane assembly was moved in/out 20 times per multiwire. Using 2 Bronson transit optical systems, the position of the central wire (transverse) and the position of the edge of the wire frame were found to be accurate to ± 50 μm .
- Need to verify similar performance for 45° mounting.

Near Term Effort

- New ceramic boards have been ordered. Expect to have a prototype wire plane assembly for testing by Dec. 1st 2003.
- Tension tests using 0.001" AuW wire, mechanical assembly and referencing should be completed by the end of December 2003.
- Modifications to the vacuum can to reduce vacuum distortion can commence at anytime; if a decision is made to do this.

Delta Deliverables by Fermilab for Plan B

- Fermilab provided equipment:
 - Fermilab Modified Multiwires 5+spare (BD Instrumentation)
 - Need to complete development and modification design work
 - Need to procure/fabricate 6 modified multiwires (vacuum cans on hand)
 - Can drop 2 standard multiwires
 - For UT Profile monitors 5+spare (BD Instrumentation)
 - Need to provide UT with vacuum can and motor assemblies design data
 - Readout Electronics (BD Controls)
 - No different from Baseline Plan
 - Motion Control for Fermilab Multiwires and UT Profile Monitors (BD Instrumentation)
 - Need to procure parts and assemble additional 10 control units
 - Motion Control for UT Foil Devices (BD Controls)
 - 2 devices in Plan B, relative to 5 devices in Baseline
- Fermilab provided support for UT Profile Monitors and Foil Devices
 - Similar as for baseline plan except long-term maintenance of two UT devices

Delta Fermilab Manpower Requirements


- BD Instrumentation (management, assembly, install, UT device support)
 - Gianni Tassotto - 40% -> 60% through Sept '04
 - Engineering Dan Schoo - 25% -> 50% through Sept '04
 - Technician Rick Pierce - 25% -> 50% through Sept '04.
- PPD or BD Vacuum Support (vacuum certification of beamline devices)
 - Similar to Baseline plan
- Alignment Group Measurement and Fiducialization
 - Similar to Baseline plan
- BD Mechanical Department
 - Similar to Baseline plan - 1 week during installation in summer '04
 - Additional 1 man month for design of 45° mounting stands
- BD Controls (signal readout and motion control)
 - Similar to Baseline plan

Estimated Delta Plan B M&S Cost

-
-
-
- Modification to vacuum can \$500 x 6 \$3000 minus 6 UT cans
 - Motor assemblies \$2000 x 6 \$12000 minus 6 UT motors
 - 6" top flange (with feedthroughs) \$1200 x 6 \$7200 minus 6 UT cans
 - Varian rotary feedthrough \$650 x 6 \$3900 minus 6 UT drives
 - Wire frame & support shaft \$2500 x 6 \$21000 minus 6 UT frames
 - Wire plane assembly & wiring \$350 x 6 \$2100
 - Total: \$49,200 minus \$UT ??? costs

 - UT absorbs cost of producing Fermilab cans/drives for their 6 units
 - Costs remain for UT development of linear drive foil devices, for incorporating SEM foils into standard Fermilab can, and ???

Time estimate



Plan B Risks and Other Costs

- Technical risk – probably few (*editorial: except UT may have very tough time designing SEM profile device compatible with constraints of Fermilab can*)
- Schedule risk – probably small, but only if decision to proceed is prompt
- Other cost – same manpower is expected to support accelerator beamline instrumentation and to be available for commissioning and operation of SY120; that level of support will be reduced
- Operational cost - increased beam losses relative to baseline UT SEM profile monitor

Conclusion and Caveat

- R&D of modified designs could be completed by end of January 2004.
- Production of modified Fermilab multiwires for NuMI could commence in January 2004 and be ready for installation in the summer 2004.
- This plan should be comfortably doable by identified Fermilab resources, but not without some cost in terms of dollars and re-direction of manpower. (We are not hoping to do this for lack of other work!)
- “Notice to proceed” is required by December 1, 2003 if schedule is to be met.

My Observations on NuMI Instrumentation

- NuMI instrumentation effort overall would benefit by identification of full-time, 100% duty factor, "instrumentation czar" who could organize and manage efforts with eye to project requirements, engineering considerations, schedule, and manpower availability
- BD Instrumentation does not have person available to do this
- Requirements for instrumentation systems to "qualify" MI beam as acceptable for extraction to NuMI are not defined! The ability to qualify the beam has been identified as very important.
- Detailed specifications of signals or data to be provided to beam permit system by instrumentation systems are not documented.
- Instrumentation Department has not been involved in definition of specifications or identification of resources for applications software; are these activities happening elsewhere?