
#### **Beam Monitoring System Overview**

#### Components:


Co-Level 3 Managers: 1. 1 Hadron Monitor Sacha Kopp – U.Texas, Austin 2. 3 Muon Monitors Debbie Harris -- Fermilab Support Structures Fire Door Gas System 5. Electronics **HV Supplies** SWIC Controllers Hadron Monitor Decay Pipe Absorber Muon Hadron Monitor Signal&HV Cables Monitors (4 types depending on location) 10 20 30 40 feet Muon Monitor Cables 6" Cable Tray (Signal: twisted flat, HV: RG58) Accelerator Clock & Ethernet 12" Cable Tray

#### **Hadron Monitor**



#### **Hadron Monitor Construction**

(Univ. of Texas – Austin, S.Kopp)




front window




rear feedthrough base

### Hadron Monitor Support Structure



Support will be provided by 2 6" I-beams Each I-beam measures 12'x6"x4", <200lbs if Al

### Hadron Monitor I-Beam Support





Leveling pads allow easier alignment (located upside down in figure)

#### Muon Monitor Chambers


- 1 chamber: 50 lbs
- 27 chambers total,9 per alcove
- Stacked together,
  would be
  8' long x 4' tall
  x 4 wide'
- Each one contains9 Am sources for calibration
- Gets shipped to rad safety first, then to us



At University of Texas-Austin: D.Indurthy, M.Lang, S. Mendoza, L.Phelps, M.Proga, N.Rao, R.Zwaska

### Muon Monitor Supports

(Univ. of Wisconsin -A. Erwin)




Will be transported underground in ~16 pieces

Heaviest Single Piece: 141 lbs, most others 50lbs or less

## First Alcove: Support Pedestal


• Alcove 1 Monitor stands higher off the ground than alcoves 2 and 3, needs a pedestal



### Beamline Monitoring Electronics

- Expect to use 3-4 racks
- Droege High Voltage Supplies
- Standard Beamline SWIC Scanners
- Stuff racks upstairs then transport them downstairs
- Located in hallway downstream of fire door





Fire Door

## Beamline Monitoring Gas System


 Helium Gas during normal running, may be Argon in the beginning for commissioning

#### •Final Configuration

- -8-pack near base of shaft
- −1 gas rack near electronics

-4 lines out of rack to absorber location and each alcove

- -Split to 9 lines in each alcove
- -Vent to exhaust in alcoves
- -Vent to exhaust for Had.Mon.



# **Summary of Components**

Component (# if more than one)	Final Location	Weight	Size
Hadron Monitor	Upstream of Absorber	40lbs	3.5'x3.5'x6"
Had. Mon. Support	Upstream of Absorber	Few hundred pounds	12'x6''x4'' I-beams + hardware
Muon Monitors (27)	Alcoves 1,2,3	50lbs each	7'x2"x6"
Muon Mon. Support (3)	Alcoves 1,2,3	Many pieces, heaviest 141lbs	Biggest piece 9.5'x5'x0.5'
Cables (signal, HV)	Access Tunnel	-	
Electronics Racks (3-4)	Access Tunnel	Few hundred pounds-stuffed	Standard Rack Size
Gas System	Access Tunnel, Base of shaft, Alcoves, before Absorber		1